



THE DISTRICT COUNCIL OF FLACQ

Notification of Award of Procurement Contract FLACQ/IFB/2026/437 (OAB/02/2025/2026)

Notice under section 40(7) of the Public Procurement Act

This is to notify that, following the bidding exercise carried out by the District Council of Flacq for **DESIGN AND BUILT OF A MULTI-PURPOSE SHELTER AT BON ACCUEIL (Ref No: FLACQ/IFB/2026/437 (OAB/02/2025/2026))**, the contract has been awarded to **SILVER ACE BUILDERS LTD** of **77, Calcutta Street, Port Louis** as per table below submitted in accordance with the instruction to Bidders.

SN	BRIEF DESCRIPTION OF WORKS	TOTAL AMOUNT (EXCLUDING VAT) (RS)
1.	Architectural Drawings	150,000
2.	Civil / Structural Drawings	150,000
3.	Design calculations	150,000
4.	As built Drawings	50,000
5.	Construction of a Multi- Purpose Shelter at Bon Accueil with steel Structure of a surface area of 625 metre square the minimum dimension will be 25m LONG X 25m WIDE with minimum EAVE height of ceiling to be 4.0m and minimum pitch roof height to be 2.0m. As per as per approved specification. The proposed structure should be single span structure. The rate shall include for the architectural and structural design, supervision works the construction works, labor costs, all materials costs, equipments costs and all other cost arising thereof	3,950,000

6.	Substructure (incl excavation in all type of soil/rocks for footing, foundation. Concreting of foundation, bases for metal section including all reinforcement and fixing works. (including anchor bolts and nuts). The flooring will be the existing asphalt tarmac in case of damaged the contractor same has to be reinstated.	1,000,000
7.	Superstructure – supply and fix steel roof, steel rafter, steel purlin, steel column, steel beam, prepainted ZincAlum profile metal sheeting on roof and rear sides (thickness to be determine as per design)	5,000,000
8.	Painting works - painting of the steel structure steel roof rafter – purlins – column beam	150,000
9.	Lighting Works- Internal and External Lighting, with low energy bulb	100,000
10.	Construction of a movable podium 7m long and 3m wide with steel section.	150,000
11.	Geotechnical investigation - assessment	150,000
12.	Supply and fix panel fence 1.8m high (25m on Right Hand Side including 2 small sliding gates 2m wide each, 25m left Hand Side including 2 small gates 2m wide each, 25m left hand side including 2 small sliding gates 2m wide each, 25m on frontage including a sliding gate 6m wide and the rear side to be fully bounded with pre painted ZincAlum Profiled Metal Sheeting thickness as per design.	200,000
	BIDDER TO PROVIDE A CONTINGENCY SUM OF RS 500,000	500,000
	TOTAL AMOUNT (Excluding VAT)	11,700,000
	VAT	1,755,000
	TOTAL AMOUNT (INCLUDING VAT)	13,455,000


D. REECHAYE
CHIEF EXECUTIVE

DATE: 16th MARCH 2026